

Shed Site Preparation



1 Check grade difference with laser transit and remove sod.



2 Additional digging so that site is level and gravel can be added.



3 Approximately 4" of stone is added and compacted.



4 Shed is delivered and placed.

- All stone pads include leveling existing site, install 4'-6' of #2 crusher run gravel compacted with skidsteer tracks.
- Access to site is assumed if a shed is able to be delivered. Skidsteer needs 7' wide access.
- Pad sites that have more than 12" slope may incur additional charges.

- Site preparation does not include final landscaping or hauling away any dirt off site. Additional cost will apply for any of these services.
- Please discuss with your sales person for a quote.